



## **Street Cut and Right of Way Permit Guidelines**

Street cut Permits for asphalt and concrete will not be issued during cold months or while local hot mix asphalt plants are not in production, as determined by the Public Works Director. This is typically late October through April depending on the weather. Any Cuts in between the edge to center line of roadway must be made to the center of the roadway and any cuts beyond center line must be patched completely across the street with a minimum width of 10'. All cuts shall either be parallel or perpendicular to the roadway. Each permit may have special conditions associated with the project depending on the situation.

Town Code, Section 11-58 states that the Town Manager or Public Works Director may require the installation of empty shadow conduit for any street cut permit to be installed by the permit holder or contractor. Failure to comply will result in the permit not being released and/or the bond(s) or other securities will not be returned.

No complete road closures are allowed at any time and all projects must keep one lane open for emergency vehicles and local traffic. Work hours are 7am -7pm Monday through Saturday with no back-up alarms allowed before 8am. Holiday work will need Town approval. All Trenches/Cuts need to be backfilled at the end of each workday with both lanes safely opened back up to traffic.

A Traffic Control and Staging Plan must be submitted on a separate piece of paper or on an approved Site Plan. The Traffic Control plan will need to show locations of all traffic control devices, works zone, area of staging, location of material to be staged, show streets with names, adjacent intersections, advanced warning signage, taper lengths, lane widths and access, and shall follow MUTCD standards. When closing a sidewalk, a submitted drawing showing an ADA compliant detour route along with the appropriate signs and barriers for this detour which the contractor or traffic control company must provide. These plans will need approval from both the Police and Fire Department prior to Public Works being able to sign off, please allow extra time for this. All parties will need a minimum of three days to review the street cut application, traffic control plan, and other attachments. Police, Fire, and area Private Property Owners who will be affected by the project need to be notified of the work taking place, hours, and given the contractors phone number at least 48 hours in advance of any work starting. Be sure to take this minimum 5-day window of review, notification, and payment processing when it is time to apply. The Town reserves the right to have their appointed engineer review any plans, specifications, or do on-site inspections at any time and pass those costs (not included in the permit fees) on to the permit holder or owner.

The Security Deposit will not be returned without a final inspection and Geo Tech compaction test results. To schedule call the Public Works Department at 970-927-4723 at least 24 hrs.in advance.

Permit# \_\_\_\_\_

EXPIRES 30 DAYS FROM ISSUE

Owner Name (Property)	Contractor Name and Company Name
Address	Address
City/State/zip	City/state/zip
Phone/ Fax	Phone #
Email	Email:
Mailing Address (If Different)	Contractor License #

### Project Information

Address of Work Location	Type of work: trenching ___ boring ___ open cut ___
	Purpose: WATER SEWER GAS ELECTRIC PHONE OTHER
	ATTACH SKETCH OF PROJECT WITH DIMENSIONS ON SEPERATE SHEET
START AND END DATE	WORK HOURS

### Deposit Calculation for Areas Being Disturbed

Area of asphalt @ \$25.00 S.F. _____ Length _____ Width = \$ _____
Area of concrete @ \$30.00 S.F. _____ Length _____ Width = \$ _____
Area of Road base @ \$ 8.00 S.F. _____ Length _____ Width = \$ _____
Area of grass @ \$ 8.00 S.F. _____ Length _____ Width = \$ _____
_____ Linear feet of curb and gutter @ \$ 25.00 L.F. = \$ _____
<b>Total Deposit Amount = \$ _____</b>
<b>Non Refundable Permit Fee = <u>\$100.00</u></b>
<b>Non Refundable Inspection Fee = <u>\$50.00</u></b>
<b>TOTAL AMOUNT DUE INCLUDING DEPOSIT AND FEES = \$ _____</b>

**Warranty and Reimbursement Agreement**

In accepting this permit the undersigned property owner and/or contractor has applied for an excavation permit pursuant to Chapter 11.03 of the Town of Basalt Municipal Code and Sec.222.3, 2612.3 and 2626 of the Town of Basalt Public Works Manual. In consideration of the issuance of such a permit, each of the undersigned hereby warrant and guarantee all materials, labor and workmanship utilized in the backfilling, compacting, repairing, and resurfacing of area where cuts and excavation are made, to be free from any failing for a period of two (2) years from the date of repair and resurfacing. In the event that failing occurs within the said time period, including subsidence or damage to the asphalt, the undersigned shall promptly repair or replace defective work or materials, at the undersigned's sole expense, in a manner satisfactory to the Town. All work and materials provided under the warranty shall be further warranted for a period of (2) years from date of acceptance by the Town.

Further, Owner agrees to pay the Town in full for all special services provided or actual costs incurred by the Town in relation to the Project or activity described herein on receipt of an itemized billing for those services from the Town (e.g. engineering and legal costs). Such amounts may be deducted from Owner's deposit; however, if insufficient to cover the costs of such services, all such amounts are due within thirty (30) days of the date of the bill, with interest on any overdue amounts to be assessed at one and one-half percent (1.5%) per month.

(CONTRACTOR AND OWNER BOTH NEED TO SIGN AND AGREE TO CONDITIONS ABOVE)

**CONTRACTOR** Representative (Print) \_\_\_\_\_  
Date \_\_\_\_\_  
Signature \_\_\_\_\_

**Property Owner** Name (Print) \_\_\_\_\_ Phone# \_\_\_\_\_ Date \_\_\_\_\_  
Address \_\_\_\_\_  
\_\_\_\_\_  
Signature \_\_\_\_\_

Town of Basalt Representative (Print) \_\_\_\_\_ Date \_\_\_\_\_  
Signature \_\_\_\_\_

**Checklist Needed Prior to Review**

Traffic Control Plan \_\_\_\_\_

Staging of Materials/Equipment Plan \_\_\_\_\_

Proof of Employee and Public Liability Insurance Attached \_\_\_\_\_

Sketch Plan of Work to be Performed and Disturbed Areas \_\_\_\_\_

Utility Line Locates \_\_\_\_\_

Landscape Plan (if needed) \_\_\_\_\_

Tree Removal Permit (if tree removal required) \_\_\_\_\_

Cedar Network Contacted and Plans submitted for Conduit Installation per Town Code \_\_\_\_\_

Traffic Control Company: \_\_\_\_\_ Phone # \_\_\_\_\_

Geo Tech Engineering Company for Compaction Testing: \_\_\_\_\_

Paving and or Concrete Company Doing Repairs: \_\_\_\_\_

Track-Out, Dust Control, Storm Water Control, and Final Clean up Description and Methods:

---

---

---

---

---

Plan for Notifying Neighboring Properties and or Community:

---

---

---